BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

BBMP/2018-19/OW/WORK_INDENT34385

Providing Street lights and maintenance in Ward No.11 Kuvempunagara

SNo	Quantity	Item Name	Unit	Rates quoted by Sri. S SOMASHEKAR	
				In figures	In words
1	15.00	Supply and erection of .....Mtr RCC Pole including earth work etc,. complete as per the standard technical specification of BESCOM 8Mtr 145Kg WL	Nos	6047.00	Rupees Six Thousand Forty Seven Only
2	25.00	LED Street light.Supply of LED Streetlight with pressure die cast aluminum housing body with optimal heat sink for better thermal dissipation. Diffuser with Injection moulded & is made of polycarbonate material with high transmission index, delivering superior light output. Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminare > IK08. Power Factor >0.9 with mains Current should not be greater than 0.1A to 0.7A & Surge Protection- Min 4KV along with Over voltage/Overload, short circuit/ miswiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with .....W System Power consumption. LED Efficiency>130lm/w at 1W & FixtureEfficiency >80lm/w with nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 . Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 5 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED source manufacture. Suitable for B1/B2 Roads as per IS 1944 Part I & Part II.LED Streetlight .LED Streetlight 24watts	Each	7000.00	Rupees Seven Thousand Only
3	80.00	65watts	Each	19500.00	Rupees Nineteen Thousand Five Hundred Only
4	103.00	Supplying and Fixing of.....mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires. Using 32mm dia G.I.pipe	Each	893.00	Rupees Eight Hundred Ninety Three Only
5	300.00	Wiring for lighting/power circuit using one of PVC insulated 1100v grade stranded Aluminium unsheathed wire single core/multi core cable in open or consealed system of wiring. a)4 sqmm.	Each	7.50	Rupees Seven And Paise Fifty Only
6	600.00	Supplying of 1.1kv grade Aerial Bunched cable stranded & compacted Aluminium Phase conductor and Stranded Messenger conductor with all aluminium alloy, Phase conductor is insulated with XLPE compound insulated Messenger with specified IS - 14255:1995 & confirming to GTP of group A. 2 X 25 + 1 X 25 SQ.MM	Per Mtr	143.00	Rupees One Hundred Forty Three Only
7	600.00	Stringing of 1.1kv LT Arial Bunched Cable, BESCOM	Per Mtr	10.30	Rupees Ten And Paise Thirty Only

Somashekhar
Contractor

Executive Engineer
Project Division
Yelahanka Zone
6/3/19

	uantity	Item Name	Unit	Rates quoted by Sri. S SOMASHEKAR	
				In figures	In words
8	7.00	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop-Out terminals for 10 Sqmm / 25 Sqmm 3.5 C Al/Ar / Cu/Ar Cable and branch out 2.5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets.200mmx200mmx98mm	Nos	2178.00	Rupees Two Thousand One Hundred Seventy Eight Only
9	7.00	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) THREE POLE 100Amps25kA.	Nos	4044.00	Rupees Four Thousand Forty Four Only
10	40.00	Open Conduit Systeme: Supplying heavy gauge PVC conditpipe,,,,,,,,,, dia confirming to IS 2509 with suitable size bends,junction boxes, adhesibve paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall stone structure or rawl plug incase of brick walls and cement plastering damaged portion using heavy gauge saddles at an interval of 700mm using NF screws. c)25mm dia 2mm thick	Mtrs	70.00	Rupees Seventy Only
11	10.00	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. And M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. A)40x40x6mm.	Mtrs	263.00	Rupees Two Hundred Sixty Three Only
12	2000.00	Supplying and stringing of ACSR Conductor (6/2.59mm Al +1/2.59mm Steel).	Mtrs	30.00	Rupees Thirty Only
13	40.00	Supplying and Fixing .....including all Hardware's etc. complete as per the standard technical specification of BESCOM 1.1 KV Pin Insulator	Nos	44.00	Rupees Forty Four Only
14	40.00	No. 8 Strain Insulator	Nos	14.00	Rupees Fourteen Only
15	48.00	Supply and fixing of .....cross arm including all Hardware's complete as per the standard technical specification of BESCOM. 2 Pin 45x45x5mm -510mm	Nos	306.00	Rupees Three Hundred Six Only
16	39.00	Fixing halogen/metal halide / SVL / IL / LED floodlight fitting over existing pole / wall ceiling including clamps, bolts, nuts and wiring using suitable capacity wires.	Nos	176.00	Rupees One Hundred Seventy Six Only

Somasekhar
Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Rates quoted by Sri. S SOMASHEKAR	
				In figures	In words
17	9.00	Supplay and erection of Single phase Thyristor based smart street light control system consisting of following aquipments 1. Precise turn ON & OFF of street lights on pre programmed data 2. 2 x 16 character LCD display unit to display date, status ON Or OFF , turn ON & OFF time, 3. Keypad to set/edit ON & OFF time as per the end user 4. Microcontroller with Real Time Clock and associated hardware 5. 1 No, SCR 162 amps thyristor module for load switching mounted on an extruded alluminium heat sink 6. Thyristor Driver Card: Driver control circuit to switch ON & OFF the Thyristor module 7. Firmware: Firmware to control the hardware and display the required data 8. Power Supply: AC to DC conversion circuit required for the electronic circuitry and driver control card 9. Enclosure is made out of 18 swg CRCA ms sheet of size H480xW310XD200mm with luvers for Heat dissipation IP65 weather proof metal enclosure 10. Wiring & other components like wiring, connectors ,insulators, Alluminium Bus bar and 2 nos of 125 amps single pole MCB for main power Supply control and Manual On & off operation & etc complete.	Set	35000.00	Rupees Thirty Five Thousand Only
18	500.00	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanished, steel wire/steel tap armoured cable with PVC outer sheating 1.1 KV class.I. Class 'A' PVC Cable. 4 core 16 sqmm	Per Mtr	140.40	Rupees One Hundred Forty And Paise Forty Only
19	500.00	Labour charges for laying of 1.1 KV class UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall /on pole as required. I. In existing trench/duct. 6 sqmm to 16 sqmm	Per Mtr	10.80	Rupees Ten And Paise Eighty Only
20	425.00	Digging of trench of 0.6 m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc.,complete. (As perCivil SR KSRB I-2, P-7).a) In soil (ordinary)	Per Mtr	78.00	Rupees Seventy Eight Only
21	1.00	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947.100-125Amps	Each	9915.00	Rupees Nine Thousand Nine Hundred Fifteen Only
22	1.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 40-63Amps TPN	Each	1936.00	Rupees One Thousand Nine Hundred Thirty Six Only
23	1.00	Supplying and fixing of Twin Dial electro mechanical timer (without contactor) using necessary bolts, nuts and washers etc.. Group A, PWD SR 2007-08,	Each	4200.00	Rupees Four Thousand Two Hundred Only
4	25000.00	Fabricating supplying and mounting MS box made out... SWG suitable lfor floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size cdlamps with mecessary cable entry pipe with gland and box should be finished with 2 cdoats of red oxide primer paint and finally finished with approved colour enameled metal pain etc., complete. b)16 swg	Nos	0.33	Rupees And Paise Thirty Three Only
5		GST @ 12%			

Somasekhar
Contractor

3

Executive Engineer
Project Division
Yelahanka Zone
6/2/19

3/19